




**RETIS**  
CONSTRUCTION

**ASSEMBLY DRAWING**


SCALE 1:100



**TYPICAL TOWER W2000F/H24**


**SECTION 1-1**

SCALE 1:50



**SECTION 2-2**

SCALE 1:50



**NOTES :**

1. Typical tower construction W2000F/H24
2. Aluminum alloy: EN AW-6005A T6
3. Connections segments: flange connection
4. Angel plate linked with fillet weld
5. Characteristic wind speed:  $V_k=22\text{m/s}$
6. Terrain category: II
7. Reliability class: II
8. Ice density:  $700\text{kg/m}^3$
9. Ice thickness: 2,0cm
10. Equipment total weight limit on the tower: 120kg
11. Equipment area on the tower:  
-  $S=1,70\text{m}^2$  at the top of the tower
12. Tower weight (with ladder): 344kg
13. Safety rail system: SKC BLOCK
14. Working platform: optional
15. Tower must be set under construction law
16. Construction on which tower will be located must be able to transfer reactions
17. Lead assembly with wind speed not more than 5m/s

<b>Manufacturer:</b>			
RETIS WWW.RETIS.PL WWW.MASZTY-RETIS.PL			
<b>Investment:</b>			
SERIES OF ALUMINUM LATTICE TOWERS - TYPE- 2000F			
<b>Drawing title:</b>			
TYPICAL TOWER W2000F/H24 - ASSEMBLY DRAWING + SECTIONS			
<b>Date:</b>	<b>Phase:</b>	<b>Project No.:</b>	<b>Revision:</b>
02.2013	typical project	RETIS W2000F	...
<b>Industry:</b>	<b>Project No.:</b>		
construction	RETIS_KK_W2000F_H24		